

Plotted

Plotted Texas

Boopman

THE TEXAS CO.
F.A.Bemis No. 12A.

SEC. 28 T. 11 R. 17W
NW SE NE
990' fr S & EL NE $\frac{1}{4}$

Total Depth. 3543'

Comm. 8-20-37 Comp. 10-17-37

Shot or Treated. 2000 & Re-acidized 1000 & 2000

Contractor. Helmerich & Payne

Gals. NOV 13 1937

Issued. 11-13-37

Rotary O-3526

CASING:

Cable 3526-43

16"

30'


10"

1213'

7"

3516'

County. Ellis



Elevation.

Production. Pot. 788 B.

Figures Indicate Bottom of Formations.

surface	39
shale blue	240
sand	320
shale	505
shale & shells	760
shale & red rock	1104
shale	1204
anhydrite	1248
shale & lime	1310
shale & shells	1515
shale, shells, red bed & salt	1690
shale & lime shells	1840
lime	1942
lime & shale	2015
lime	2326
shale & lime	2522
lime	2574
shale	2594
shale & lime	2650
shale & shells	2723
shale	2792
lime	2815
brkn lime	2860
shale & shells	2885
shale & lime	2942
lime	3122
shale	3134
lime	3139
brkn lime	3212
lime	3490
shale green	3499
shale green sdy	3510
sand	3516
lime	3526
Siliceous lime	3543
Total Depth.	