


THE TEXAS COMPANY
F.A. Bemis No. 13-A

SEC. 28 T. 11 R. 17W.
SE NW NE
990' fr N and W.L. NE $\frac{1}{4}$

DEEPENING RECORD

Total Depth. 3926'
Comm. 9-3-37 Comp. 9-30-37
Shot or Treated. Not acidized.
Contractor. J.E. Trigg Drlg. Co.
Issued. 12-16-39

County Ellis.



CASING.

16" 31' Rotary 3393
103/4" 1110' Cable 3926
7" 3393'

Elevation.

408' 53/16" osg set for liner at 3199'

Production. Pot. 1638 B.

Figures Indicate Bottom of Formations.

surface	31	Top Arbuckle 3393
shale and shells	465	Top Reagan Sand 3875
sand	540	
shale and shells	660	Hole bridged from 3600
sand	750	to 3625
shale	1103	
lime	1148	
shale and shells	1340	
lime	1390	
shale	1409	
salt	1645	
shale and shells	1780	
lime	1902	
broken lime	2020	
lime	2043	
shale and shells	2111	
lime	2283	
shale	2303	
lime	2380	
sdv shale	2479	
shale and shells	2702	
lime	2760	
shale	2810	
lime	3353	
broken lime	3369	
shale	3372	
lime	3380	
shale green	3390	
Simpson sand	3393	
lime	3400	
Total Depth.		

DEEPENING RECORD

Comm. 7-30-39 Comp. 8-28-39
Contractor. Chas. Trapp
Production. Salt Wtr Disp.

dolomite	3400-3730
sand	3755
dolomite	3860
dolomite sdv	3875
sand	3924
granite	3926
Total Depth.	