

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

L.H. WENTZ - JONES BROS. DRUG. CO.
Fred A. Bemis No. 2

SEC. 28 T. 11 R. 17W.
SE NE NW

DEEPENING RECORD

Total Depth. 3989
Comm. 6-22-37 Comp. 7-24-37
Shot or Treated.
Contractor.
Issued. 6-21-47

County Ellis.

CASING.

15 1/2" 80' 8" 5 1/2" Liner 3386-3576 Cem.
10" 1194' w/50 sx. Elevation. 1953 set
7" 3459'

Production. Pot. 3036 B

Figures Indicate Bottom of Formations.

cellar	6"	broken lime	2806
shale and shells	80	broken lime and shale	2878
no log	99	shale	2890
sticky shale	179	broken lime	2925
sticky shale&shells	445	lime	3440
shale and shells	653	shale green	3455
shale	700	Simpson show oil	3459
broken iron hard sand	719	shale green	3461
sand	749	lime	3466
shale and red bed	838		
shale	845	Total Depth.	
shale red	865		
shale and red bed	935		
red bed and shale	990		
shale red bed	1070		
red rock	1105		
shale	1125		
red rock	1160		
red rock and shale	1173		
par. of iron	1178		
anhydrite	1190		
anhydrite	1217		
red rock	1300		
shells and shale	1585		
salt and shells	1627		
salt	1695		
shale and shells	1735		
broken lime	1787		
lime	1860		
shale and lime	1892		
lime hard	1960		
lime and red rock	2065		
lime hard	2080		
lime	2345		
shale	2355		
lime	2505		
broken lime	2626		
lime	2645		
shale	2664		
broken lime	2704		
broken lime and shale	2771		

DEEPENING RECORD:

I. P. - Input: 195 BPH, 20"
vacuum.
T. D. - 3989'
Comm. - 4-1-47
Comp. - 4-30-47
Acidized w/1000 gals.

dolomite	3567
chert & dolomite	3585
dolomite	3629
dolomite sdy	3690
dolomite	3787
sand	3826
dolomite sdy	3916
sand	3931
dolomite sdy	3934
sand	3984
sand & granite	
wash	3989

Total Depth.

Tops:

Arbuckle	3459
Keagan	3916
Granite Wash	3984