


L.H. WENTZ (OIL DIVISION)
Fred A. Bomis No. 4.

SEC 28 T. 11 R. 17W.
SEC NW

SEP 18 1937

Total Depth, 3432
Comm. 7-13-37 Comp. 8-10-37
Shot or Treated.
Contractor.
Issued 9-18-37

County Ellis.



CASING.

15 1/2" 74'10
7" 3416'

Elevation.

Production. Pot. 2434 B.

Figures Indicate Bottom of Formations.

shale	88
cement	90
shale and shells	400
red bed	450
sand	510
shale and shells	650
sand	750
shale and shells	915
red bed and shells	1065
shale	1135
chalk	1140
anhydrite	1157
cavity	1168
anhydrite	1190
sdv shale	1207
shale and shells	1510
shale and salt	1590
salt	1700
shale and shells	1777
broken lime & shale	1930
sdv shale	1965
sdv shale and limo	1985
sdv shale	2040
shale and limo	2055
broken limo	2142
sdv limo	2200
limo	2220
shale and limo	2260
sand	2276
limo	2310
porous limo	2322
shale shells & cavities	2390
shale and limo	2504
broken limo	2560
broken shale & limo	2590
sand shale & shells	2640
no log	2725
shale and shells	2755
limo	2800
broken limo and shale	2825
shale and shells	2846
shale and limo	2910
limo	3432

Total Depth.