


WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - HARRY M. LIGGETT
Farm - Madden No. 2.

SEC. 29 T. 11 R. 17 W
NEc NE

Total Depth. 3628 PB 3380
Comm. 2-2-45 Comp. 3-12-45
Shot or Treated.
Contractor.
Issued. 1-26-46

County. Ellis
KANSAS



CASING:
8 5/8" 1257' Cem.
5 1/2" 3567' Cem.

Elevation. 2042 ft

Production. Temp. Abnd.

Figures Indicate Bottom of Formations.

surface rock & shale 40
shale 100
shale, lime & shells 200
shale & shells 370
pyrite & shale 408 ✓
sand & pyrite 555 ✓
lime, shale & pyrite 590 ✓
sand 690
iron & lime 710 ✓
shale, lime & pyrite 785 ✓
sand 950
shale, shells & red
bed 1170
red bed 1205
shale, shells &
red bed 1265
anhydrite 1307
red bed & shale 1455
shale & shells 1635
salt 1785
salt & shale 1925
lime 1935
lime & shale 2065
shale & shells 2110
lime & shale 2320
lime 2340
lime brkn 2420
lime & shale 3055
lime 3200
lime & shale 3225
lime 3535
lime & shale 3558
cherty conglomerate 3569
lime 3583
lime ? 3628
Total Depth

Plugged back 3380