


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- CHAMPLIN REFINING COMPANY
Farm- Ladley "L" No. 6

SEC. 30 T. 11 R. 17W
C SW NW SE
1650' fr SL & 330' fr WL of
SE/4
County

Total Depth. 3630'
Comm. 9-21-56 Comp. 10-5-56
Shot or Treated.
Contractor.
Issued. 3-2-57

Ellis
KANSAS



Elevation. 2099'

Production. 80 BOPD

CASING:

8 5/8" 2217' w/150 sx cem. none pulled
5 1/2" 3629' w/100 bbls mixture none pulled

Figures Indicate Bottom of Formations.

post rock	35
sand & River	
Gravel	100
shale	295
shale & red bed	640
fine sand	740
coarse sand	
& Pyrite	850 ✓
sand	995
shale & shells	1275
red bed &	
shells	1336
Anhydrite	1378
shale & shells	1875
shale w/lime	
strks	2070
shale/ w/lime	
strks & salt	2155
shale & lime	3187
lime	3236
lime & shale	3317
lime	3407
lime & shale	3415
lime	3458
lime & Pyrite	3483 ✓
lime & shale	3522
lime	3551
lime & shale	3594
lime & chert	3615
lime	3630
Total Depth	

TOPS	
Dakota Sand	640
Base/Dakota	955
Anhydrite	1332
Base/Anhydrite	1372
Topeka	3043
Heebner	3270
Toronto	3292
Lansing	3319
Base/Kansas	
City	3558
Cherty	
Conglomerate	3588
Arbuckle	3596