

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

Plotted JS

AMERADA PETROLEUM CORP.
C.M. Hadley No. 2

SEC. 31 T. 11 R. 17W.
CW¹/₂ NW SE

Total Depth. 3663.
Comm. 5-24-40 Comp. 6-13-40
Shot or Treated. 500 gallons acid 6-23-40
Contractor. Creekmore Drig. Co.
Issued. 8-10-40

County Ellis



CASING.

95/8" 1085' cemented.
7" 3658' cemented

Elevation.

Production Pot. 1197 B.

Figures Indicate Bottom of Formations.

surface clay	80
shale blue	410
shale	505
sand	545
shale	690
sand	750
shale	885
sand	995
shale blue	1015
shale	1112
red bed	1354
anhydrite	1395
red shale	1607
red bed and shale	1860
shale	1980
lime	2080
shale	2180
Ft. Riley lime	2390
lime	2500
shale	2530
lime	2665
shale	2680
lime	2780
shale	2884
broken lime	2917
shale	2945
lime	3015
broken lime	3097
lime	3454
lime cored	3466
lime	3605
shale	3616
conglomerate	3626
shale green	3630
dolomite	3643
shale green	3657
Arbuckle lime	3663
Total Depth.	

GEOLOGICAL TOPS.

FT. Riley	2180
Topeka	3075
Lansing lime	3367
Conglomerate	3616
Simpson shale	3625
Arbuckle	3657