

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
 508 East Murdock, Wichita, Kansas


Company- WALTERS DRILLING
 Farm- Hadley "C" No. 1

SEC. 31 T. 11 R.17W
 C SE $\frac{1}{4}$

Total Depth. 3662'
 Comm. 10-2-54 Comp. 10-15-54
 Shot or Treated.
 Contractor. Walters Drlg. Co.
 Issued. 11-20-54

County Ellis

KANSAS



Elevation. 2111' DF

Production. Dry

Figures Indicate Bottom of Formations.

surface	176
shale-shells	860
sand	1020
shale-shells	1356
anhydrite	1398
shale-shells	1870
s hale-lime	2259
lime	2433
lime-shale	3420
lime	3605
lime-conglomerate	3642
shale-lime	3662 RTD
Total Depth	

TOPS :	
Anhydrite	1356
Topeka	3087
Heebner	3318
Lansing-Kansas City	3367
Conglomerate	3611
Simpson	3634
Arbuckle	3657

5 $\frac{1}{2}$ " set @ 3658'. M.I.C.T .
 Cleaned out hole to show joint
 bad cement job. Recemented w/50
 sx. 1500# pressure. Cleaned out
 to bottom. Acidized w/500 gals.
 Hourly tests 50% wtr.