


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

Company- MURFIN DRILLING COMPANY
Farm- Hadley "H" No. 1

SEC. 31 T. 11 R. 17W
NW S^W NE

Total Depth. 3707'
Comm. 2-11-57 Comp. 2-23-57
Shot or Treated. 3000 A
Contractor. Murfin Drilling Company
Issued. 5-4-57

County Ellis KANSAS



Elevation. 2114' KB

Production. Dry

Figures indicate Bottom of Formations.

shale, shells	500
sand, shale, shells	545
shale, shells	650
sand, shale, shells	725
shale, shells	800
sand, shale	1005
red bed, shale	1354
Anhydrite	1391
shale, shells	1805
shale, lime, shells	2005
lime, shale	3363
lime	3555
lime, shale	3648
lime, Arbuckle	3660
Arbuckle	3664
lime, shale,	
Arbuckle	3700 RTD
lime, shale,	
Arbuckle	3707
Total Depth	

TOPS	
Anhydrite	1354
Topeka	3079
Heebner	3310
Toronto	3330
Lansing/Kansas City	3358
Conglomerate	3610
Simpson	3623
Arbuckle	3648

DRILL STEM TEST

DST #1 3649-65' 1 hr.

Rec. 105' watery mud

BHP 210#.

DST #2 3665-90' 1 hr.

Rec. 150' watery mud

BHP 350#.