


WELL LOG BUREAU — KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk. Bldg., Wichita, Kansas

Company - YORK STATE OIL COMPANY  
Farm - Hadley No. 1

SEC. 32 T. 11 R. 17W  
NE SW

Total Depth. 3623'  
Comm. 6-28-47 Comp. 7-18-47  
Shot or Treated.  
Contractor.  
Logged. 9-13-47

County. Ellis  
KANSAS



Elevation. 2109 *act & sh*

Production. Phy. Pot. 97 BO

CASING:

8" 1337' Cem. w/600 sx  
5 1/2" 3613' Cem. w/100 sx

Figures Indicate Bottom of Formations.

lime & surface clay	45
shale & sand	205
shale & shells	630
sand & shale	760
shale & lime	867
sand & lime	958
lime sdy	1060
red bed & shale	1105
red bed	1180
sand & shells hrd	1285
red bed & shale	1325
anhydrite	1370
shale & lime	1690
shale & red rock	1750
shale & lime	1993
lime	2055
lime brkn & shale	2110
shale & lime	2230
lime	2460
shale & lime	2490
lime	2695
shale & shells	2715
lime & shale	2935
shale & shells	3062
lime	3072
lime & shale	3171
lime	3312
lime & shale	3360
lime	3527
lime & red rock	3594
shale & lime	3618
shale green & xyln dol brwn	3620
dolomite brwn xyln cherty w/fair sat.	3623
Total Depth	

Tops:

<del>Tops</del>	3080
Kansas City	3365
Dolomite	3595
Simpson	3610
Arbuckle	3612

Oil Shows:

3200-3210  
3290-3313  
3365-3380  
3390-3395  
3430-3450  
3490-3500  
3510-3515  
3612-3623