


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- MURFIN DRILLING COMPANY
Farm- Hadley "G" No. 1

SEC. 32 T. 11 R. 17W
SW NW NW

County Ellis

KANSAS



Total Depth. 3700'

Comm. 1-30-57

Comp. 2-10-57

Shot or Treated.

Contractor. Murfin Drilling Company

Issued. 4-27-57

CASING:

8" @387' w/200 sx cem.

Elevation. 2099' KB

Production. Dry

Figures indicate Bottom of Formations.

shale, shells	495	
sand, shale shells	525	
red rock, shale, shells	680	
shale, shells	840	
sand	990	
red bed, shale	1333	
Anhydrite	1368	
shale, shells	1705	
salt, shale	1860	
shale, lime, shells	2105	
lime, shale	3360	
lime	3578	
Conglomerate	3700	RTD
Total Depth		

TOPS	
Anhydrite	1333
Topeka	3054
Heebner	3286
Toronto	3312
Lansing/Kansas City	3332
Conglomerate	3578

DRILL STEM TEST

DST #1 3332-80'

Mis-run, packer didn't hold

DST #1-A 3322-80' op. 1/2 hr.
op. 1/2 hr. Rec. 65' muddy
salt wtr. BHP 1250#.

DST #2 3414-30 3/4 hr.
Rec. 25' mud BHP 700#.