

33-11-17W

BEMIS "B" # 3

#13 ✓

York State Oil Co., Inc.,
 Contractor: Ted Ferrier
 Elevation: 2009'
 Total Depth: ~~3525~~ 3531'
 Spudded: 9-2-46
 Completed: 9-25-46

Location: NE NE NW 33-11-17W
 Ellis County, Kansas
 Potential: 259 Bbls per day
 No water
 Taken 10-23-46
 This is a drillers log. The samples were lost.

130	Surface clay & shale	Drilled in with cable tools to
553	Shales & Shells	3531 T.D.
675	Sand	
785	lime & sand	Acidized w/500 gal - filled up
955	sand & lime	2000' in 2 hours
1175	shale and shells	
1234	red bed and shale	Top of Arbuckle 3519'
1270	Anhydrite	
1505	red bed, shale and shells	Casing Record:
1630	red bed and shale	8-5/8" 1228'
1690	shale and salt	5 1/2" 3522'
1840	shale and shells	
2125	lime and shale	
2180	lime	Test taken 5-5-47 well made
2200	lime, sandy	170 bbls per day
2210	lime	
2273	lime and sand	
lime	2355	
2370	shale and shells	
2410	lime and shale	
2460	lime and sand	
2480	broken lime	
2620	lime	
2660	shale and shells	
2705	lime	
2766	shale and shells	
2800	lime	
2835	shale and shells	
2900	lime	
2935	shale	
3090	lime	
3122 3132	lime and shert	
3260	lime	
3325	lime	
3340	broken lime	
3362	broken lime	
3497	lime	
3519	Simpson sand3	
3521	Simpson sand	
3522	Arbuckle	

RECEIVED
 STATE CORPORATION COMMISSION

JAN 26 1989

CONSERVATION DIVISION
 Wichita, Kansas

RECEIVED
 STATE CORPORATION COMMISSION

FEB 02 1989

JAN 26 1989

KANSAS GEOLOGICAL SURVEY
 WICHITA BRANCH
 CONSERVATION DIVISION
 Wichita, Kansas