


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk Bldg., Wichita, Kansas

WOLF CREEK OIL CO.  
Bomis "D" No. 2.

SEC. 33 T. 11 R. 17 W  
CW  $\frac{1}{2}$  NE SE

Total Depth. 3580'  
Comm. 3-20-43 Comp. 4-22-43  
Shot or Treated.  
Contractor. Wolf Creek Oil Co.  
Issued. 5-22-43

County. Ellis



CASING:  
10 $\frac{3}{4}$ " 80' LI  
53/16" 3472' (LI 529'3")

Elevation.

Production. Dry

Figures Indicate Bottom of Formations.

shale	90
shale & shells	480
sand	570
shale & shells	785
sand	910
shale & shells	925
red bed	1225
shale & shells	1260
anhydrite	1295
lime brkn	1310
shale & shells	1670
salt & shale	1740
shale & shells	1800
lime brkn	2210
lime	2357
shale & lime	2395
lime brkn	2535
shale & shells	2598
lime & shale	2630
shale & shells	2923
shale & lime	2982
lime brkn	3005
lime	3095
lime-chert	3131
lime	3195
limo brkn	3222
lime & chert	3580
Total Depth.	

Tops: K.C.Lime 3240  
Conglomerate 3480

Oil Show:  
After acid oil from 3337-49  
about 5 bbl. in 24 hr. w/5  
bbl. wtr per hr  
Slight stain 3446-48