

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - SOHIO PETRO. CO.
Farm Bemis "F" No. 7

SEC. 33 T. 11 R. 17 W
NW NE NE

Total Depth. 3592'
Comm. 9-27-46 Comp. 10-19-46
Shot or Treated.
Contractor.
Issued. 12-21-46

County. Ellis
KANSAS



Elevation. 2083 *nh 9 set*

Production. Pot. 139 BO, no wtr.

CASING:

13 3/8" 70' Cem.
8 5/8" 1307' Cem.
5 1/2" 3587' Cem.

Figures Indicate Bottom of Formations.

rig foundation &	
cellar	0-10
lime brkn	40
shale	90
shale & shells	150
shale	260
shale & shells	550
sand	585
shale	760
sand & shale	815
sand	840
shale & red bed	1000
shale, shells & red bed	1297
anhydrite	1350
shale & shells	1940
lime brkn	2315
lime	2375
lime brkn	2590
shale & shells	2750
shale	2835
lime brkn	2970
shale & shells	3015
shale	3045
lime	3160
shale	3193
lime	3592
Total Depth.	

Tops:
Anhydrite 1297
Arbuckle 3585