


Company - THE TEXAS COMPANY
Farm - C. Dreiling No. 2

SEC. 34 T. 11 R. 17W
SW SW SE

Total Depth. 3588'
Comm. 12-21-47 Comp. 1-27-48
Shot or Treated. acidized
Contractor. Stickle Drlg. Co.
issued. 2-28-48

County. Ellis
KANSAS



Elevation. 2085 m
2083 ind

Production. Pmp 137 BO no wtr.
first 24 hours.

Figures indicate Bottom of Formations.

rock & shale	50	1-24-48	CO at 3586', 1200' oil in hole
shale blue & sand	220	1-25-48	Co & swabbing. Making 4 BOPH, no wtr.
shale blue	250		
lime & shells	280		
shale & shells	475		
sand	510		
shale & shells	610		
shale	700		
shale & sand	810		
shale & shells	850		
sand	930		
shale & shells	945		
shale, lime & sand	990		
shale red & shells	1282		
anhydrite	1335		
shale & shells	1700		
salt	1860		
shale & shells	1960		
lime broken	2000		
shale & shells	2095		
lime & shale strks	2200		
lime broken	2340		
lime & shale	2395		
lime	2495		
lime & shale	2960		
shale & shells	3030		
lime broken	3070		
lime	3182		
lime broken	3205		
lime	3588		

Total Depth

TOPS:

Topeka	3028
Heebner	3263
Lansing	3332
Simpson	3558
Arbuckle	3567

- 12-22-47 Drilling to 610', lost circulation at 40'. Cem. Crevice.
- ~~12-21-47 Drilled to 825'. Cem. crevice W/25 Sx.~~
- 1-5-48 Ran Schlumberger.
- 1-12-48 Acid W/100 gal, swabbing, making 1 1/4 BOPH, no wtr.
- 1-13-48 Drilled to 3588'. Filled up 400' in 1 hr. Swabbed 2 1/2 BOPH for 6 hr.
- 1-15-48 Ran tubing. Acid W/500 gal. Max Press 600#, Mim press 500#.
- 1-18-48 Pipped 69 Bbls. oil.
- 1-19-48 Pmp 132 B in 11 hr, 78 bbl load, 5 1/4 bbl new oil.
- 1-20-48 Pmp 50 Bbls oil in 4 hours.
- 1-21-48 Pmp 34 bbls in 8 hours.
- 1-23-48 Put in 3' rock, 3 sx Calseal, filled up 19'. Loaded hole W/66 bbls oil. Shot from 3575 to 3588 W/30 qts. solidified Hercules W/zero omb, shell size 4" X 13'.