

KANSAS

State Geological Survey
WICHITA, BRANCH

WELL COMPLETION REPORT AND
DRILLER'S LOG OLD WELL WORK OVER


S. 34 T. 11S R. 17 ^{EX}W

API No. 15 _____
County _____ Number _____

Loc. SE/4 SE/4 SW/4

County Ellis

640 Acres
N



Elev.: Gr. 2103

DF 2106 KB 2106

Operator
Cities Service Company

Address
209 East William, Wichita, KS 67202

Well No. 4 Lease Name Hauser "A"

Footage Location 330' N - 330' W of S/4 Corner
feet from (N) (S) line feet from (E) (W) line

Principal Contractor Golden B. Hydra Drilling, Inc. Geologist A. R. Glen

Spud Date 4-21-48 Date Completed 6-2-80 Total Depth 3643' P.B.T.D. 3643'

Directional Deviation Not directionally drilled Oil and/or Gas Purchaser Cities Service Company

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8-5/8"	-	355'	Surface pipe	cemented	Filed 4-21-48 as per report.
Production	7-7/8"	5 1/2"		3599'		150	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
TUBING RECORD			SEE ATTACHED		
Size 2 1/2"	Setting depth 3599	Packer set at NONE			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
See attached	

INITIAL PRODUCTION

Date of first production 6-2-80 Producing method (flowing, pumping, gas lift, etc.) Pumping

RATE OF PRODUCTION PER 24 HOURS
Oil 33 bbls. Gas - MCF Water 268 bbls. Gas-oil ratio NONE CFPB

Disposition of gas (vented, used on lease or sold) No gas from well Producing interval (s) -----

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Well No. 4	Lease Name Hauser "A"	Oil
S 34 T 11S R 17 ^X W		


WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Re-entry of old well. Drillers log attached to plugging record filed in 1973.				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	 E.W. Peterman Signature Region Operations Manager Title Date
---------------	--

90004

Cont. 34-115-17w

34-11-17w
C50
Hausen "A" #4

ACIDIZING RECORD

"K"	3531'-35'	750 gallons	15% NE Acid
"J"	3503'-05'	500 gallons	15% NE Acid
"I"	3485'-89'	750 gallons	15% NE Acid
"H"	3468'-70'	500 gallons	15% NE Acid
"G"	3420'-24'	750 gallons	15% NE Acid
"D"	3376'-79'	500 gallons	15% NE Acid
"B"	3364'-66'	500 gallons	15% NE Acid
"A"	3328'-30'	500 gallons	15% NE Acid

Cont.
34-115-17w

34-11-17w
CSO
Hausner "A" #4

PERFORATION RECORD

			<u>SHOTS</u>	<u>SIZE</u>
L-KC	"A" Zone	3328' - 30' (2')	4	2½"
L-KC	"B" Zone	3364' - 66' (2')	4	2½"
L-KC	"D" Zone	3376' - 79' (3')	6	2½"
L-KC	"G" Zone	3420' - 24' (4')	8	2½"
L-KC	"H" Zone	3468' - 70' (2')	4	2½"
L-KC	"I" Zone	3485' - 89' (4')	8	2½"
L-KC	"J" Zone	3503' - 05' (2')	4	2½"
L-KC	"K" Zone	3531' - 35' (4')	8	2½"