

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas


Company - CITIES SERVICE OIL CO.
Farm - Johansen "B" No. 2

SEC. 34 T. 11 R. 17 W
CE/2 NW NW
660' S & 990' E of NW Cor.

Total Depth. 3655'
Comm. 10-23-46 Comp. 12-21-46
Shot or Treated. Acidized
Contractor. Veeder Sup. & Dev'l Co.
Issued. 2-8-47

County. Ellis

KANSAS



Elevation. 2083 ft + nh

Production. Dry

CASING:

12 $\frac{1}{2}$ " 90' Cem. w/100 sx.
8 5/8" 1112' Cem. w/350 sx.
5 $\frac{1}{2}$ " 3613' Cem. w/100 sx.

Figures Indicate Bottom of Formations.

lime	0-40
shale & shells	500
sand & pyrite	530 ✓
shale & shells	619
pyrite	623 ✓
pyrite & shale	650 ✓
sand & shale	720
shale & lime	852
sand	940
sand & shale	1010
shale & shells	1035
red bed & shells	1060
shale & shells	1310
anhydrite	1342
shale	1375
shale & salt	1530
shale & shells	1880
lime & shale	1955
shale & shells	2025
lime & shale	2110
shale & shells	2330
shale	2355
shale & shells	2480
shale & lime	2530
shale & shells	2620
lime & shale	2660
shale	2735
shale & shells	2845
shale & lime	2885
shale & shells	3080
lime & shale	3220
lime brkn	3265
lime & shale	3350
lime	3555
conglomerate	3620
lime	3628

3628 RTD=3618 SLM

Solomite 3655

Total Depth.

Corr. Top Arbuckle 3611
Penetration 44

2/3 BOPH 3629'

2 $\frac{1}{2}$ BF ($\frac{1}{2}$ oil) per hr 3644

3 BF (mostly water) per hr.

3655

12-24-46 - Pmpd 49 BF (30%
wtr.) 24 hrs.

12-29-46 - Pmpd. 29 BF (59%
wtr.) 24 hrs.

Acidized w/500 gals. acid 12-15-46

@ 3629'

Acidized w/500 gals. acid 12-22-46

@ 3655'.