

36-11-17W


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 E. Murdock, Wichita, Kansas

Company - ANDERSON PRICHARD OIL CORP.
Farm - Hall "C" No. 1

SEC. 36 T. 11 R. 17W
NW NE SW

Total Depth. 3621
Comm. 9-20-49 Comp. 10-8-49
Shot or Treated.
Contractor. Birmingham-Bartlett
Issued. 4-29-50

County. Ellis
KANSAS



Elevation. 2102 (m)
2104 RB (End)

Production. Pot. 40 bbls no wtr.

CASING:

13 3/8" 116' cem w/125 sx.
8 5/8" 130'3' cem w/100 sx.
5 1/2" 3608' cem w/150 sx.

Figures indicate Bottom of Formations.

white rock, shale	118
shale, shells	635
sand	740
shale, shells	860
sand	900
shale, shells	1265
redbed, shells	1290
anhyd.	1325
shale, shells	1905
lime, shale	2175
lime brkn	2505
lime, shale	3165
lime	3600
cong.	3607
lime RTD	3609
lime	3621
Total depth	

Tops:

Anhydrite	1290
Heebner	3280
Lansing	3328
Conglomerate shale	3590
Conglomerate chert	3595
Arbuckle	3607

Remarks:

Dlg. plug, Drilled 3609-11, no free oil. Show in samples. Drilled 3611-21, V.S.S.O. Good odor in samples. 500 acid 1100# to 200#. Swbd 20 bbls oil, no water/12 hrs. Swbd 25 bbls oil, no water /24 rhrs. Reacidized w/1000 gals. Swbd 3 BOPH/ 8 hrs. no water