


12-11S-18W



## DRILL STEM TEST REPORT

Prepared For: **Venture Resources Inc**

PO Box 101234  
Denver CO 80250

ATTN: Greg Mackey

**12 11S 18W Ellis KS**

**Ridler A-West # 8**

Start Date: 2008.06.15 @ 02:56:11

End Date: 2008.06.15 @ 09:52:41

Job Ticket #: 32777      DST #: 1

Api # 15-051-25744-0000  
W2 NE NW NW  
330 FNL 865 FNL

Trilobite Testing, Inc  
PO Box 1733 Hays, KS 67601  
ph: 785-625-4778 fax: 785-625-5620

Venture Resources Inc

Ridler A-West # 8

12 11S 18W Ellis KS

DST # 1

Arbuckle

2008.06.15



**TRILOBITE  
TESTING, INC**

## DRILL STEM TEST REPORT

Venture Resources Inc

PO Box 101234  
Denver CO 80250

ATTN: Greg Mackey

**Ridler A-West # 8**

**12 11S 18W Ellis KS**

Job Ticket: 32777

DST#: 1

Test Start: 2008.06.15 @ 02:56:11

### GENERAL INFORMATION:

Formation: **Arbuckle**

Deviated: No Whipstock: ft (KB)

Time Tool Opened: 04:45:41

Time Test Ended: 09:52:41

Interval: **3436.00 ft (KB) To 3446.00 ft (KB) (TVD)**

Total Depth: 3446.00 ft (KB) (TVD)

Hole Diameter: 7.80 inches Hole Condition: Good

Test Type: Conventional Bottom Hole

Tester: Jason McLemore

Unit No: 32

Reference Elevations: 1940.00 ft (KB)

1933.00 ft (CF)

KB to GR/CF: 7.00 ft

**Serial #: 6719**

**Inside**

Press@RunDepth: 19.25 psig @ 3438.00 ft (KB)

Start Date: 2008.06.15

End Date:

2008.06.15

Start Time: 02:56:13

End Time:

09:52:41

Capacity: 7000.00 psig

Last Calib.: 2008.06.15

Time On Btm: 2008.06.15 @ 04:44:41


Time Off Btm: 2008.06.15 @ 08:01:41

TEST COMMENT: IFP Weak surface blow building to 1/8 "

ISI Dead

FFP Dead

FSI Dead



### PRESSURE SUMMARY

| Time (Min.) | Pressure (psig) | Temp (deg F) | Annotation           |
|-------------|-----------------|--------------|----------------------|
| 0           | 1728.15         | 101.62       | Initial Hydro-static |
| 1           | 15.28           | 101.23       | Open To Flow (1)     |
| 17          | 16.19           | 100.68       | Shut-In(1)           |
| 77          | 30.17           | 100.95       | End Shut-In(1)       |
| 78          | 16.45           | 100.96       | Open To Flow (2)     |
| 144         | 19.25           | 101.80       | Shut-In(2)           |
| 196         | 22.00           | 102.44       | End Shut-In(2)       |
| 197         | 1671.41         | 102.93       | Final Hydro-static   |

### Recovery

| Length (ft) | Description       | Volume (bbl) |
|-------------|-------------------|--------------|
| 1.00        | liter Min sampler | 0.01         |
|             |                   |              |
|             |                   |              |
|             |                   |              |
|             |                   |              |
|             |                   |              |

### Gas Rates

|  | Choke (inches) | Pressure (psig) | Gas Rate (Mcf/d) |
|--|----------------|-----------------|------------------|
|--|----------------|-----------------|------------------|



**TRILOBITE  
TESTING, INC**

## DRILL STEM TEST REPORT

**TOOL DIAGRAM**

Venture Resources Inc

**Ridler A-West # 8**

PO Box 101234  
Denver CO 80250

**12 11S 18W Ellis KS**

Job Ticket: 32777

**DST#: 1**

ATTN: Greg Mackey

Test Start: 2008.06.15 @ 02:56:11

### Tool Information

Drill Pipe: Length: 3432.00 ft Diameter: 3.80 inches Volume: 48.14 bbl  
Heavy Wt. Pipe: Length: 0.00 ft Diameter: 2.70 inches Volume: 0.00 bbl  
Drill Collar: Length: 0.00 ft Diameter: 2.25 inches Volume: 0.00 bbl  
Total Volume: 48.14 bbl

Tool Weight: 2000.00 lb  
Weight set on Packer: 25000.00 lb  
Weight to Pull Loose: 50000.00 lb  
Tool Chased 0.00 ft  
String Weight: Initial 42000.00 lb  
Final 42000.00 lb

Drill Pipe Above KB: 27.00 ft  
Depth to Top Packer: 3436.00 ft  
Depth to Bottom Packer: ft  
Interval between Packers: 10.00 ft  
Tool Length: 41.00 ft

Number of Packers: 2 Diameter: 6.75 inches

Tool Comments:

| Tool Description | Length (ft) | Serial No. | Position | Depth (ft) | Accum. Lengths                |
|------------------|-------------|------------|----------|------------|-------------------------------|
| Change Over Sub  | 1.00        |            |          | 3406.00    |                               |
| Shut In Tool     | 5.00        |            |          | 3411.00    |                               |
| Sampler          | 3.00        |            |          | 3414.00    |                               |
| Hydraulic tool   | 5.00        |            |          | 3419.00    |                               |
| Jars             | 5.00        |            |          | 3424.00    |                               |
| Safety Joint     | 2.00        |            |          | 3426.00    |                               |
| Packer           | 5.00        |            |          | 3431.00    | 31.00 Bottom Of Top Packer    |
| Packer           | 5.00        |            |          | 3436.00    |                               |
| Stubb            | 1.00        |            |          | 3437.00    |                               |
| Perforations     | 1.00        |            |          | 3438.00    |                               |
| Recorder         | 0.00        | 8360       | Outside  | 3438.00    |                               |
| Recorder         | 0.00        | 6719       | Inside   | 3438.00    |                               |
| Perforations     | 5.00        |            |          | 3443.00    |                               |
| Bullnose         | 3.00        |            |          | 3446.00    | 10.00 Bottom Packers & Anchor |

**Total Tool Length: 41.00**



**TRILOBITE**  
**TESTING, INC**

## DRILL STEM TEST REPORT

### FLUID SUMMARY

Venture Resources Inc

**Ridler A-West # 8**

PO Box 101234  
Denver CO 80250

**12 11S 18W Ellis KS**

Job Ticket: 32777

**DST#: 1**

ATTN: Greg Mackey

Test Start: 2008.06.15 @ 02:56:11

### Mud and Cushion Information

Mud Type: Gel Chem

Cushion Type:

Oil API:

deg API

Mud Weight: 9.00 lb/gal

Cushion Length:

ft

Water Salinity:

ppm

Viscosity: 50.00 sec/qt

Cushion Volume:

bbl

Water Loss: 7.80 in<sup>3</sup>

Gas Cushion Type:

Resistivity: ohm.m

Gas Cushion Pressure:

psig

Salinity: 2100.00 ppm

Filter Cake: inches

### Recovery Information

Recovery Table

| Length<br>ft | Description        | Volume<br>bbl |
|--------------|--------------------|---------------|
| 1.00         | liter M in sampler | 0.014         |

Total Length: 1.00 ft

Total Volume: 0.014 bbl

Num Fluid Samples: 0

Num Gas Bombs: 0

Serial #:

Laboratory Name:

Laboratory Location:

Recovery Comments:

# Pressure vs. Time

