

KANSAS WELL LOG BUREAU --- KANSAS GEOLOGICAL SOCIETY

508 EAST MURDOCK - WICHITA, KANSAS

COMPANY BAY PETROLEUM CO.

SEC. 1 T. 11 R. 18W

FARM Barbier 'A'

NO. 5

LOC. NW NW NW

TOTAL DEPTH 3542

COMM. 1-18-51

COMP. 1-29-51


SHOT OR TREATED

CONTRACTOR Pickrell Drlg. Co., Inc.

ISSUED 4-7-51

COUNTY Ellis

KANSAS



CASING

8 5/8" 190' cem. w/100 sx

5 1/2" 3539' cem. w/250 sx

ELEVATION

1990 (m)
1992 RB Ind.

PRODUCTION I.P.P. 54 BO NW

FIGURES INDICATE BOTTOM OF FORMATIONS

cellar	5
rock & shale	160
shale & shells	765
sand	980
shale & shells	1285
anhydrite	1320
shale & shells	1820
lime	1900
lime broken & shale	2140
lime	2425
lime & shale	2585
lime	2660
lime & shale	2970
lime	3540 RTD
lime	3542
Total Depth	

Tops:	
Heebner	3172
Toronto	3190
Lansing	3212
Conglomerate	3458
Arbuckle	3538

Circulate for samples @	3287
" " "	3400
" " "	3438
" " "	3473
" " "	3528
" " "	3534
" " "	3538
" " "	3540

DST: 3397-3436- open 40 mins.
weak blow in 10 mins. rec. 10'
rotary mud. V.S.S.O. on test
tool. No BHP.

DST: 3458-71, open 45 mins. weak
blow in 10 mins. rec. 10' mud.

No BHP

Measurements from top rotary
bushing.