

110000
E.M.

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bank Bldg, Wichita, Kansas.

C. J. BAY
Ridler No. 4-B.

SEC. 1 T. 11 R. 18W.
CW $\frac{1}{2}$ NW SE

Total Depth. 3477
Comm. 6-10-40 Comp. 7-4-40
Shot or Treated. 3000 gal acid.
Contractor. Crow Drilling Co.
Issued. 9-7-40

County Ellis



CASING.

13" 78' Cemented to top.
85/8" 1210' Cemented to top.
5 $\frac{1}{2}$ " 3470' Cemented.

Elevation.

Production. Pot. 5695 B.

Figures Indicate Bottom of Formations.

surface clay and shale	91	lime	3055
shale and lime shells	481	lime shale & red rock	3060
sand (Dakota)	516	lime grey and white	3090
shale and lime shells	672	lime and red rock	3100
shale	710	lime & shale breaks	3105
sand	878	lime white	3120
shale and lime shells	1201	lime and green shale	3130
anhydrite	1245	lime and shale breaks	3145
shale	1249	lime and chert	3155
shale and lime shells	1464	lime and shale breaks	3175
shale	1487	lime grey and white	3280
salt	1727	lime and chert	3305
shale	1739	lime and shale breaks	3345
shale	1767	lime	3410
shale and lime shells	1878	shale brown, red and	
shale	1915	green	3415
lime shells	1943	lime	3425
lime	1977	lime & variegated	
shale	1992	shale	3435
broken lime	2041	conglomerate	3445
lime	2110	Simpson dolomite and	
shale and lime shells	2166	shale	3455
lime	2205	shale green	3470
broken lime	2261	chert and dolomite	3474
lime and chert	2297	dolomite	3477
lime	2317		
shale and lime shells	2384	Total Depth.	
shale	2404		
shale and lime shells	2450		
lime	2466		
shale	2498		
lime	2525		
shale	2716		
lime	2743		
shale	2769		
shale lime shells	2820		
shale red rock & lime	2830		
shale and lime streaks	2870		
lime grey and white	2990		
lime grey and brown	3010		