

WELL LOG BUREAU — KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas


Company - MIDSTATES OIL CORP.
 Farm - Cross No. 7

SEC. 2 T. 11S R. 18W
 NW SW SE

Total Depth. 3602'
 Comm. 6-7-47 Comp. 6-26-47
 Shot or Treated.
 Contractor.
 Issued. 9-13-47

County. Ellis

KANSAS



Elevation. 1971 *act rd*

Production. Dry

CASING:

10 3/4" 1286' Cem 650 sx

Figures Indicate Bottom of Formations.

Sand	25
Shale and shells and sand	190
Shale and shells	460
Sand and shale	520
Sand	610
Shale and shells	740
Sand	940
Shale and shells	1215
Red Bed	1280
Anhydrite	1325
Red Bed and shells	1700
Red bed and salt	1790
Shale and shells	1920
Shale and lime	2525
Lime	2600
Shale and lime	2985
Lime	3010
Shale and lime	3095
Lime	3155
Lime and shale	3215
Lime	3285
Lime and shale	3320
Lime	3430
Conglomerate	3520
Chert, lime, shale	3555
Arbuckle	3558
Chert & lime	3568
Lime, chert & shale	3602
Total Depth	

TOPS:

Anhydrite	1280
Topeka	2941
Lansing	3235
Conglomerate	3476
Simpson	3526
Er. Arbuckle	3536
Arbuckle	3546
Total Depth	3600