


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- CONTINENTAL OIL CO.
 Farm- Watkins No. 7

SEC. 2 T. 11 R. 18W
 C S/2 SW SE NW
 2529' fr NL, 1650' fr WL NW/4
 County Ellis

Total Depth. 4035
 Comm. 2-17-53 Comp. 3-13-53
 Shot or Treated.
 Contractor. Strain Drilling Co.
 Issued. 7-4-53

KANSAS



Elevation. 1976 RB

Production. S. W. D. V.

CASING:

9 5/8 set at 1286' w/ 500 sx cement
 7 in. set at 3617' w/ 4505 sx cement

Figures Indicate Bottom of Formations.

All RB measurements

clay & post rock	40
shale	240
shale & shells	550
red bed & shale	600
sand	650
shale & sand	760
sand	945
shale, red bed & shells	1040
red bed & shale	1284
anhydrite	1318
shale & shells	1830
lime & shale	1900
lime	1930
shale & lime	2265
lime	2300
lime & shale	2325
lime	2350
lime & shale	2800
lime	2835
shale & lime	2985
lime	3439
Simspon lime & shale	3452
lime	3526
Arbuckle	4035
Total Depth	

Schlumberger ran log to TT.

TOPS:

Anhydrite	1318
Beebner	3166
Lansing KC	3209
Base KC	3447
Simspon	3452
Arbuckle	3526

DST #1: 3351-83, open 10 min. BHP
 15 min.--misrun.

DST #2: 3351-83, open 1 hr. rec.
 945' muddy salt water, 15 min.
 BHP 1200#, FP 225#

DST #3: 3403-10, open 1 hr. rec. 30'
 rotary mud, 15 min. BHP 0#

DST #4: 3496-3518, open 1 hr., 8 min
 weak blow, rec. 6' rotary mud. BHP 0#

DST #5: 3527-49, open 1 hr. 11 min
 weak blow, rec. 10' drlg mud. 15 min.
 BHP 190#

Cored:
 3279-3309; 3356-83; 3392-3408, 3410-39,
 3498-3518, 3518-48, 3549-63, 3563-75,