

4-11-18W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- PETROLEUM, INC.
Farm- Warner "D" No. 2

SEC. 4 T. 11 R. 18W
SW NE NE

Total Depth. 3520'
Comm. 12-10-62 Comp. 12-21-62
Shot or Treated.
Contractor. Garvey Drig. Co.
Issued. 7-13-63

County Ellis
KANSAS



CASING:
8 5/8" 256' cem w/175 sx.
4 1/2" 3514' cem w/150 sx.

Elevation. 2002' DF

Production. 81 BOPD, TR. WTR.

Figures Indicate Bottom of Formations.

surface soil & rock	85
shale	570
sand	650
shale	880
sand	960
shale	1030
shale & sand	1150
red bed	1296
anhydrite	1334
shale, red bed & shells	1680
shale	1980
shale & shells w/sandy lime	2220
lime	2485
shale & lime	2625
lime & shale	2760
shale & lime	2935
lime & shale	3050
lime	3520
Total Depth	
TOPS: LOG	
Anhydrite	1300
Heebner	3148
Toronto	3166
Lansing	3191
Arbuckle	3512