

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk Bldg., Wichita, Kansas

Plotted  
E.M.


11-11-18 W

R. G. BERRY ET AL  
Carmichael No. 2.

SEC.11 T.11 R.18W  
CSL NW SE  
330'N SL 660'E WL NW SE

Total Depth. 3442 $\frac{1}{2}$ '  
Comm. 7-23-41 Comp. 8-13-41  
Shot or Treated. None  
Contractor.  
Issued. 10-11-41

County. Ellis



CASING:  
8 $\frac{1}{4}$ " 1211' Cem.  
5 $\frac{1}{2}$ " 3438 $\frac{1}{2}$ ' Cem.

Elevation.

Production. Pot. 3000 B.

Figures Indicate Bottom of Formations. Drawdown

cellar	10	Tops:	
shale	95	Topeka	2900
shale & shells	435	Lansing-K.C.	3160
sand & shale	485	Cherty Conglomerate	3400
sand	545	Simpson	3420
iron	575	Arbuckle	3438 (Note-this has been corrected to derrick floor)
sand & shale	635		
lime & shale	698		
sand & shale	859		
shale sdy	870	Note: Top of Arbuckle has been corrected in "Tops" given above and in the log to derrick floor.	
lime	890	All other measurements given above and in the log are from the top of the rotary table.	
red bed & shale	930		
shale, red bed, sand	1164		
shale & shells	1207		
anhydrite	1250		
red bed, shale, shells	1525		
salt & shale	1695		
shale & shells	1753		
lime & shale	1780		
lime & anhydrite	1800		
shale & shells	1875		
lime sdy	1930		
lime & shale	2055		
lime sdy	2063		
lime	2068		
lime brkn	2165	lime cherty	3266
lime	2185	lime	3337
lime & shale	2212	lime & cherty strks	3368
shale & shells	2435	lime & shale	3401
lime & shale	2492	cherty conglomerate	3408
shale & shells	2670	conglomerate	3429
lime	2686	shale green	3437
lime & shale brks	2695	shale sdy	3438
lime brkn	2719	lime Arbuckle	3439
shale	2726	lime Arbuckle - oil	3442 $\frac{1}{2}$
lime brkn	2793	Total Depth.	
lime & shale	2827		
sand & shale strks	2858	Producing Horizon -	
lime	2929	Arbuckle lime 3438 $\frac{1}{2}$ -42 $\frac{1}{2}$	
lime, cherty strks	2966		
lime	3144		
lime & shale	3225		
lime	3236		