

9-11-18 W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company. PETROLEUM, INC.
Farm. Meistrell "D" No. 3

SEC. 9 T. 11 R. 18W
C N/2 NW NE

Total Depth. 3687'
Comm. 8-2-61 Comp. 8-14-61
Shot or Treated.
Contractor. Garvey Drlg. Co.
Issued. 1-13-62

County Ellis
KANSAS



Elevation. 2058' DF

Production. 53 BOPD

CASING:

8 5/8" 251' cem w/165 sx.
4 1/2" 3480' cem w/150 sx.

Figures Indicate Bottom of Formations.

surface soil & native rock	50
sand & shale	85
shale	256
shale & shells	500
shale, shells w/pyrite strks	1285
shale	1372
Anhydrite	1412
shale	1515
shale & shells	1830
shale	1940
lime	2040
lime & shale	2210
shale & lime	2350
lime & shale	2665
shale & lime	2965
lime & shale	3070
lime	3530
lime & chert	3605
Conglomerate	3662
Arbuckle	3687
Total Depth	

TOPS: SCOUT

Topeka	3038
Queenhill	3193
Heebner	3260
Toronto	3278
Lansing	3302
Base Kansas City	3527
Conglomerate Chert	3555
Simpson Dolomite	3612
Arbuckle	3660