

9-11-18W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
500 East Murdock, Wichita, Kansas

Company- PETROLEUM, INC.  
Farm- O'Brien "B" No. 1

SEC. 9 T. 11 R.18W  
NE NE NW

Total Depth. 3655'  
Comm. 9-2-60 Comp. 9-14-60  
Shot or Treated.  
Contractor. Garvey Drlg. Co.  
Issued. 12-31-60

County Ellis  
KANSAS



CASING:  
8 5/8" 257' cem w/250 sx.  
5 1/2" 3652' cem w/575 sx.

Elevation. 2059' DF

Production. 45 BOPD

Figures indicate Bottom of Formations.

surface soil & post rock	90
shale & shells	420
sand	520
shale & shells	790
sand	970
sand & shale	1020
red bed & shale	1370
Anhydrite	1405
shale & shells	2050
lime & shale	3015
lime	3120
lime & shale	3195
lime	3605
lime & chert	3625
shale	3640
Arbuckle lime	3655
Total Depth	

TOPS:	
Topeka	3036
Heebner	3256
Toronto	3274
Lansing	3297
Base Kansas City	3522
Conglomerate	3548
Simpson Shale	3605
Simpson Dolomite	3619
Arbuckle	3635