

11-11-18W
WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- ASH-MAR DRILLING COMPANY
Farm- Foldkamp No. 1

SEC. 11 T. 11 R. 18W
NE SE SW

Total Depth. 3447

Comm. 1-29-53


Shot or Treated.

Contractor.

Issued. 7-11-53

Comp. 6-13-53

County Ellis KANSAS



CASING:

8 5/8" 240'

Elevation. 1889

Production. 50 bbls. / 81%

Figures Indicate Bottom of Formations.

clay & gravel	35
shale & shells	550
pyrite, sand & shale	670 ✓
sand	850
shale & shells	914
shale & red bed	1035
red rock	1120
shale & shells	1170
anhydrite	1205
shale & shells	1760
lime & shale	1810
lime	2080
lime & shale	2800
lime	3087
lime & shale	3195
lime	3315
shale & lime	3378
conglomerate	3435
simpson & lime-arbuckle	
@ 3442'	3445
arbuckle	3447
Total Depth	

TOPS:	
Topeka	2866
Hoebner	3087
Kansas City Lime	3131
Conglomerate	3376
Simpson dolomite	3426
Arbuckle	3442

D.S.T. 3430 - 3447' (Halli-
burton) tool opened 2
hrs. filled 2100' with
oil - no water.
BHP - 848#
FFF - 745#

All measurements from top of RB