

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.  
412 Union National Bank Bldg, Wichita, Kansas.


12-11-18W

CENTRAL PETROLEUM CO., INC.  
Hadley No. 3

SEC. 12 T 11 R. 18W.  
NW NE SE  
990' W 330' S NEcSE $\frac{1}{4}$

Total Depth. 3362  
Comm. 11-26-39 Comp. 5-29-40  
Shot or Treated.  
Contractor. Ruso Drlg. and Okan Drlg.  
Issued. 8-24-40

County. Ellis.



CASING.

15" 106' 53/16" 3353'  
10" 1096'

Elevation.

Production. Pot. 6308B.

Figures Indicate Bottom of Formations.

No log above 1100'  
anhydrite 1100- 1170  
shale red bed 1244  
red bed and shale 1410  
lime and shale 1550  
shale 1640  
shale and S. lime 1755  
lime 1810  
shale sticky 1850  
shale sticky 1880  
sdy lime 1940  
lime and shale 1990  
shale broken 2042  
shale and lime 2100  
lime and shale 2155  
shale 2195  
sdy shale 2250  
sdy shale soft 2275  
lime and shale 2285  
shale and lime 2360  
shale and shells 2420  
shale 2493  
shale and shells 2535  
lime and shale 2681  
shale and shells 2763  
shale 2785  
lime 2942  
lime hard 2968  
lime 3085  
lime hard 3099  
soft & oil 3102  
lime hard 3113  
lime 3235  
shale cavo 3238  
lime 3240  
lime hard 3247  
lime 3260  
shale dark 3265

limo 3272 sh free oil  
limo hard 3276  
limo 3303  
shale dark 3308  
limo 3325  
shale green 3330  
limo 3340  
shale green 3345  
limo brown 3348 sh oil  
sand lime correction 3336 = 3348  
sand and iron 3353 ✓  
Arbuckle 3362  
Total Depth, Halliburton Measurement.

Acidized with 1100 gal at 3087. Well made  
1/2 bailers fluid per hr, mostly water,  
very little free Oil; At 3108 water in-  
creased considerably; At 3136 well made  
4 bbls per hr, 1/2 water. Oil coming  
from 3099 to 3102. acidized with 2000  
gallons with packer placed so acid hit  
3099 to 3102. Ran wood plug and cemented  
back up to 3040 and used Hallibuton  
jet gun to test Topeka 2983-90 A idized  
with 500 gallons. Showed only water no oil

July 17, 1940. Potential after acidizing  
with 1000 gal - 6308 B.

Tops- Anhydrite 1085  
Topeka 2800  
Lansing K.C. 3064-3136

Oil showing 2985-92