


CORRECTED LOG

Total Depth. 3358'  
Comm. 4-6-39 Comp. 5-18-39  
Shot or Treated.  
Contractor, Harry Gore  
Issued. 7-15-39

County. Ellis



CASING:

8 1/4" 2250' UR 2782'  
65/8" 3030' UR 3162'  
5" 3260' UR 3352'

Elevation.

Production. Pot. 2221 B.

Figures Indicate Bottom of Formations.

rotary hole	1095	shale blue	2962
lime anhydrite	1135	lime sdy water	2990
shale blue	1145	lime	3018
red rock	1365	shale blue	3030
slate	1445	lime Dodge	3045
salt	1672	Corrected M. from 3045-3054	
shale white	1680	shale blue	3054-3059
salt	1690	red rock	3063
shale & shells	1750	lime Kansas City	3068
lime	1765	lime Oil	3073
red rock	1775	lime	3093
lime	1820	lime Oil	3098
red rock	1835	lime	3100
lime	1865	lime Oil	3105
shale white	1875	lime	3125
red rock	1905	lime HFW	3132
lime	1945	lime	3149
shale & shells	1955	lime Oil & Wtr	3159
lime	2020	lime	3162
red rock	2040	lime wh hrd	3195
lime	2050	shale blue sft	3200
red rock	2060	lime wh hrd	3225
lime	2110	shale blue sft	3230
red rock	2120	lime wh hrd	3260
lime	2130	shale blue sft	3265
red rock	2140	lime wh hrd	3281
lime	2150	shale blue sft	3287
red rock	2165	lime med hrd	3295
lime	2180	lime wh hrd	3305
red rock	2190	lime brkn sft	3310
lime	2225	shale brown sft	3317
red rock	2237	lime wh hrd	3328
sand wtr	2250	shale green sft	3331
lime sdy	2325	lime shell hrd	3333
shale blue	2332	shale green sft	3338
lime	2335	Simpson Dolomite	3340
shale & shells	2350	shale green sft	
lime	2380	sand & iron	3352 ✓
shale blue	2370	Arbuckle 3352 1/2	3358
lime	2400	Total Depth.	
shale & shells	2485		
slate	2510	Water Record:	
shale sdy	2535	LBW 2205-15	
lime sdy	2540	HFW 2237-50	
shale & shells	2570	Wtr 2265-95	
shale blue	2600	7 BW 2375-2400	
lime	2620	HFW 2965-75	
shale & shells	2665	HFW 3125-32	
lime	2670	Oil & Wtr 3149-59	
shale	2680	3 BWPH 3230-3240	
lime	2700	Sand Record:	
shale	2710	Topeka Lime 2952-55 1 1/2 BOPH	
shale & shells	2780	K.C.lime 3068-73 2 1/2 BOPH	
shale	2815	3093-98) Filled up 2500'	
lime	2885	K.C.lime 3100-05) with oil	
shale	2890	K.C.lime 3149-59 showed 60%	
lime	2895	water 40% oil	
shale lgt	2900		
lime	2930		
slate & lime shells	2945		
lime	2958		