


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

SHELL OIL CO., INC.
E. Ridlor No. 2-A.

SEC 12 T. 11 R. 18W.
NW SW NW
992' fr SL 330' fr WL NW $\frac{1}{4}$

Total Depth. 3506=3507 SLG PB 3481
Comm. 7-3-40 Comp. 7-27-40
Shot or Treated.
Contractor.
Issued. 8-10-40.

County Ellis.



CASING.

13" 158'
85/8" 1189'
4 1/2" 3507'

Elevation.

Depthograph

Production, drawdown test of

Figures Indicate Bottom of Formations. 9510 B. no water.
Allowed Pot. of 3000 B.O.

lime and shale	250	slight porosity, slight spotted oil stain	3065-70
shale and shells	475	slight porosity in strks slight spotted	
sand	580	oil stain	3182-85
shale shells pyrite	600 ✓	fair to good porosity, fair live to	
sand and pyrite	662 ✓	dead oil stain	3232-37 and 3240-48
sand	864	slight porosity, slight spotted oil	
sand and lime strks	886	stain	3307-10
sand and pyrite	970 ✓	slight porosity, and fair spotted	
lime shale and red bed	1050	head oil stain	3348-53
shale and shells	1181	very little porosity, slight oil stain	3362-67
anhydrite	1191	little porosity, scattered heavy oil	
anhydrite	1230	stains	3414-3421
red bed	1350	slightly vagular, fair to good spotted	
shale	1550	oil stain	3433-34
salt and shale	1750		
shale and shells	1845	Top Arbuckle dolomite	3433 S.L.C.
shale lime strks	1890	slight porosity, very slight to good	
gyp and lime	1920	oil stain	3434-38
shale	1925	fair to good porosity, fair to good oil	
lime	1970	staining	3438-43
lime and shale	2110	slight porosity and good oil staining	3443-45
lime	2147	good porosity and heavy oil staining	3445-46
lime and shale	2190	strks of porosity and stain, less pay	
lime	2239	than above	3446-54
lime and shale	2335	porous, light to heavy oil staining	3454-58
shale	2480	scattered strks of porosity and showings	
lime	2602	of oil	3458-65
lime and shale	2760	good porosity, heavy oil stain	3465-69
lime	2787	much good porosity & oil stain	3469-75
2824 equals 2804 S.L.C.		little porosity and oil stain	3475-79
lime & shale	2870	strks of good porosity and oil staining	3479-87
lime	2882	some porosity, and oil stain, loss porous	
lime	2925	than above.	3487-92
2925 equals 2937 S.L.C.		poor porosity and oil stain	3492-98
lime	2982	small smount of porosity, and occasional	
lime strks of chert	3023	spotted light oil stain (water bearing)	3498-06
lime and chert	3043	perforated 3470-75' with 47 bullets	
lime and chert strks	3060	P.B. dolomite 3481. 177' oil in 1 minute	
lime	3160	2010 Oil in 19 minutes	
lime	3372	2780' oil in 43 minutes	
lime and chert strks	3398	2888' oil in 57 minutes	
Vari. Col. chert, lime		2963' oil in 1 hr and 35 Min.	
and shale no shows	3414	2965' oil in 2 hrs. and 15 Min.	
dolomite greenish grey	3421	Swab 200 oil and no water	
shale med hd& green and		4 hours 2050' off bottom.	
red strks	3433	average 50 B.O. per hr last	
dolomite	3506	2 hours 2050' off bottom.	
3506 equals 3507 SL Corr.			
Total Depth.			

Plugged Back 3481