

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg., Wichita, Kansas.

Plotted for


12-11-18 W

PHILLIPS PETROLEUM CO.
A. Sites No. 7

SEC. 12 T. 11 R. 16W.
CN $\frac{1}{2}$ SW SW

Total Depth 3364 DF.
Comm. 1-9-41 Comp. 3-5-41
Shot or Treated.
Contractor.
Issued. 5-10-41

County Ellis.



CASING.

8" 1118'
5" 3359'

Elevation.

Production. Pot. 3000 B.

Figures Indicate Bottom of Formations.

shale and shells	375
shale and sand	500
iron and lime	540 ✓
sand shale & shells	1105
anhydrite	1145
red shale	1230
shale	1495
salt and shale	1650
shale and shells	2080
lime	2130
shale and shells	2507
shale	2599
chert	2608
shale and lime shells	2729
lime	2818
shale and lime	2920
lime	3335
lime and shale	3353
lime	3364 DF.

Total Depth.

Top of Anhydrite 1105

Top of Arbuckle 3359

Cored 3167-75 Fair Por. and Sat. 67-72
- cored 3360-62 and 3362-64.
Fair to good porosity and Sat.