

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.


Plotted JS
12-11-18W

PHILLIPS PETROLEUM CO.
A. Sites No. 8.

SEC. 12 T. 11 R. 18W.
CS $\frac{1}{2}$ SW SW

Total Depth. 3363 DF.
Comm. 2-18-41 Comp. 3-26-41
Shot or Treated.
Contractor.
Issued. 5-17-41

County Ellis



CASING.

8" 1122'
5" 3359'

Elevation.

Production. Pot. 3000 B.
Maximum.

Figures Indicate Bottom of Formations.

shale and shells	520
iron pyrite	620 ✓
shale and shells	628
sand and shells	780
lime shells and shale	835
shells and red bed	1020
shells and red bed	1107
chalk	1111
anhydrite	1155
red bed and shells	1300
shale and salt	1405
shale and shells	1490
salt and shale	1580
lime and shale	1761
shale and lime shells	2100
lime	2110
lime and shale	2142
lime	2207
shale and shells	2695
lime	2730
shale and lime	2943
lime	2993
lime and shale	3043
lime	3259
lime and shale	3290
lime	3363 DF.

Total Depth.

Top of Anhydrite 1111
Arbuckle 3362 Sat. in samples.

Drilled soft 3102-3104. Cored
3104-3112. From 04-07 $\frac{1}{2}$ oolitic
lime with excellent por. and
saturation. From 07 $\frac{1}{2}$ -12 dense lime
no sat. Drilled soft 3164-66 good
porosity and sat. cored 3166-3174.
From 66-71 good por. and sat. From
71-74 dense shaly lime with some
sat.