

12-11-18W

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas


Company- PHILLIPS PETROLEUM CO.  
Farm- Sites (Twin) No. 9

SEC. 12 T. 11 R. 18W  
93' E of C S/2 SE SW

Total Depth. 3456' PB 3430'  
Comm. 5-24-61 Comp. 6-26-61  
Shot or Treated.  
Contractor. Sierra Petroleum Co.  
Issued. 9-9-61

County Ellis

KANSAS



Elevation. 1858 Est. DF

Production. 27 BO & 6 BWPD

CASING:

9 5/8" 438.50' cem w/100 sx.  
7" 3449' cem w/60 sx.  
DV Tool set @ 1118' cem w/150 sx.

Figures Indicate Bottom of Formations.

clay & sand	20
sand & shale	150
blue shale	330
sand	346
shale & sand	439
sand	545
sand & shale	755
red bed	1098
Anhydrite	1142
shale & shells	1645
lime & shale	2075
lime	2140
lime & shale	2823
lime	3349
lime & shale	3377
lime	3456 RTD

Total Depth  
Plugged back to 3430'

TOPS: ~~WELEX~~

Anhydrite (scout)	1098
Howard	2790
Topeka	2817
Heebner	3014
Toronto	3032
Lansing-Kansas City	3056
Drum	3192
Base Kansas City	3294
Simpson	3327
Arbuckle	3346