

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.  
412 Union National Bank Bldg, Wichita, Kansas.

*Plotted  
hu.*


13-11-18W

DARBY PETROLEUM CORP.  
Hadley "B" No. 7

SEC. 13 T. 11 R. 18W.  
CNL SW NW

Total Depth. 3345  
Comm. 3-5-41 Comp. 3-20-41  
Shot or Treated.  
Contractor.  
Issued. 4-12-41

County Ellis.



CASING.

15" 91'  
10" 1100'  
7" 3338'

Elevation.

Production. Pot. 3000 B.  
Maximum

Figures Indicate Bottom of Formations.

shale and sand	60
sand	75
shale	91
shale and shells	450
sand and iron	780 ✓
shale red bed	940
shale	1105
anhydrite	1145
shale & shells	1480
salt	1590
shale & shells	1785
shale & lime	1980
lime	2105
lime & shale	2420
shale	2650
shale & lime	2720
shale	2775
shale & lime	2825
lime	3345

Total Depth.

Top Arbuckle 3338

Saturation and Porosity at 3340

Drlg. cement at 3340  
2150' OIH  $1\frac{1}{2}$  hours.  
2750' OIH  $3\frac{1}{2}$  hours.  
2900' OIH 5 hours.

Drlg. deeper to 3345 T.D.  
500 acid.