

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bldg., Wichita, Kansas

Plotted gw


13-11-18W

PHILLIPS PETRO.
Wm. Hendrick No. 2

SEC. 13 T. 11 R. 18W
CN $\frac{1}{2}$ NW NE

Total Depth. 3351'
Comm. 5-14-39 Comp. 8-2-39
Shot or Treated. 500 Gals. Acid.
Contractor.
Issued. 9-9-39

County. Ellis



CASING:
13" 25'
8" 1093'
5" 3347'

Elevation.

Production. Pot. 3500 B. Max.

Figures Indicate Bottom of Formations.

surface, sand & shale	38
shale	140
shale & shells	365
blue shale, red rock & shells	630
red rock & shells	680
sand	800
sand, shale & pyrite	930
red rock & shale	1090
anhydrite	1100
red shale & anhydrite	1160
red beds	1260
red rock & blue shale	1435
salt, blue shale & red rock	1516
salt, shale & shells	1670
shale & shells	1716
shale	1725
lime gy	1785
shale & shells	2130
lime & shale brkn	2292
lime & shale brks	2357
lime	2395
brkn lime & shale	2400
lime & shale	2557
brkn lime & shale	2667
lime & shale brkn	2751
lime & shale	2811
lime	2872
lime & shale	2934
lime brkn	3015
lime & shale	3040
lime	3147
lime cherty	3149
lime w/some chert	3195
lime hrd	3221
lime brkn	3233
lime hrd	3291
lime	3351
Total Depth.	

Top Anhydrite 1087
Top Lan. K.C. 3040
Top Arbuckle 3347