

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

Plotted *gwr*
13 - 11 - 18 W


PHILLIPS PETROLEUM CO.
Wm. Hendrick No. 4

SEC. 13
CNL SE NE

T. 11 R. 18W.

Total Depth, 3360 DF.
Comm. 9-20-39 Comp. 10-25-39
Shot or Treated,
Contractor,
Issued, 7-6-40

County Ellis.



CASING.

8" 1111'
5" 3357'

Elevation.

Production. Pot. 3000 B.

Figures Indicate Bottom of Formations.

surface shale and sand	102
shale shells & sand	262
shale and shells	598
shale and sand	640
sand	772
lime and pyrite	785 ✓
shale lime shells	934
shale sand and pyrite	1036 ✓
shale and shells	1107
anhydrite	1115
anhydrite shale shells	1258
lime and shale	1547
salt shale lime	1683
shale and lime	1850
lime	1863
shale and lime	1958
lime	2008
shale and lime	2105
lime	2147
shale lime shells	2192
lime	2280
shale	2337
lime	2450
shale and lime	2565
shale	2702
shale and lime	2810
lime	2813
shale and lime	2828
lime	3076
shale and lime	3157
lime	3360
Total Depth, D.F.	

Top Anhydrite 1106

Top Lansing K.C. 3045 Good porosity and sat. 3163-73

Top Simpson 3338

Top Arbuckle 3357 good porosity & sat.