

13-11-18W

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,


Wichita, Kansas

Company- PHILLIPS PETROLEUM CO.
Farm- Peavey No. 9

SEC. 13 T. 11 R. 18W
93' West of C N/2 NW SE

Total Depth. 3481' PB 3434'
Comm. 1-18-62 Comp. 2-26-62
Shot or Treated.
Contractor. Sterling Drlg.
Issued. 6-2-62

County Ellis KANSAS



Elevation. 1910' DF

Production. 83 BO & 13 BWPD

CASING:

9 5/8" 445'
7" 3470'

Figures Indicate Bottom of Formations.

shale & shells	445
shale	540
shale & sand	905
sand & red bed	1147
Anhydrite	1175
shale & shells	1220
shale & lime	1740
lime	2385
shale & lime	2675
shale & sand	2688
lime	2693
shale & lime	2850
shale	2860
lime	3481 RTD
Total Depth	
Plugged back to	3434'

TOPS: WELEX

Waubaussee Group	2529
Tarkio	2641
Emporia	2684
Howard	2831
Topeka	2857
Haebner	3059
Toronto	3079
Lansing-Kansas City	3103
Drum	3237
Base Lansing-Kansas City	3340
Simpson Dolomite	3358
Simpson Shale	3370
Arbuckle	3380