

13-11-18W
✓


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- PHILLIPS PETROLEUM CO.
Farm- Peavey No. 10

SEC. 13 T. 11 R. 18W
NE NE SE

Total Depth. 3445' PB 3431'
Comm. 8-17-62 Comp. 9-17-62
Shot or Treated.
Contractor. Sierra Petroleum Co., Inc.
Issued. 11-17-62

County Ellis
KANSAS



Elevation. 1857' DF

Production. 29 BO & 211 BWPD

CASING:

10 3/4" 453.35' cem w/185 sx.
7" 3444' cem w/340 sx.

Figures Indicate Bottom of Formations.

Post rock	75
shale & shells	454
shale, shells & sand	860
(640' to 750' Main Dakota Sand)	
red bed & shale	1087
anhydrite	1127
shale & shells	1495
shale, shells & red bed	1650
shale & lime	2920
lime	3388
arbuckle	3444
arbuckle ?	3445
Total Depth	

PLUG BACK DEPTH 3431'

TOPS:

Heebner	3008
Toronto	3028
Lansing Kansas City	3052
Drum	3138
Base Kansas City	3290
Simpson Dolomite	3304
Simpson Shale	3322
Arbuckle	3332