

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
 412 Union National Bank Bldg, Wichita, Kansas.


*Plotted per
 13-11-18W*

PHILLIPS PETRO. CO.
 O.C. Peavey No. 3

SEC. 13 T. 11 R. 18W.
 CN $\frac{1}{2}$ NE SE

Total Depth. 3332 DF
 Comm. 11-1-39 Comp. 12-13-39
 Shot or Treated.
 Contractor.
 Issued. 2-10-40

County - Ellis.



CASING.

8" 1090' 5" 3329'

Elevation.

Production. Pot. 7332B.

Figures Indicate Bottom of Formation Depth. (3000 B. Max.)

surface	40
surface sand and shale	240
shale sand and shells	371
shale sand and pyrite	562 ✓
shale and shells	812
shale and pyrite	1072 ✓
anhydrite and shale	1090
anhydrite	1120
anhydrite and lime	1123
shale and shells	1394
shale salt and lime	1639
shale and lime	1805
shale	1868
shale and lime	2073
lime	2110
shale and lime	2331
shale	2346
shale and lime	2601
shale	2650
lime	2663
shale and lime	2800
lime	2848
shale and lime	2887
lime	2962
shert and lime	3021
lime and shale breaks	3041
lime	3332
Total Depth.	Derrick Floor.

Top of Lansing K.C. 3028
 Good sat. & porosity 3144-3150
 Top Simpson 3315
 Top Arbuckle 3329