

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
 212 Union National Bk Bldg., Wichita, Kansas

Plotted

13-11-18W

DARBY PETRO. CORP.
 Peavey No. 1-A

SEC. 13 T. 11 R. 18W
 SEc SW

Total Depth. 3411'
 Comm. 1-16-39 Comp. 2-6-39
 Shot or Treated. 2000 Gals.
 Contractor.
 Issued. 3-4-39

County. Ellis

MAR 4 1939



CASING:
 15" 115'
 10" 1157'
 7" 3396'

Elevation.

Production. Pot. 2275 B.

Figures Indicate Bottom of Formations.

shale	114
shale & shells	395
red rock	440
red bed, shale & sand	556
iron	590
shale	815
red rock & shale	1025
red rock & shells	1135
shale	1151
anhydrite	1187
shale	1290
slate	1490
shale	1550
salt	1695
shale & shells	1745
shale & lime	1890
shale & shells	1960
shale & lime	2160
lime brkn	2220
lime brkn & shale	2320
lime	2390
lime & shale	2465
lime brkn	2520
lime brkn & shale	2580
lime & shale	2710
lime	2760
lime brkn & shale	2825
lime	3400
1200' OIH 5 H. at	3400
lime	3405
2650' OIH 3 H. additional	
lime	3408
2900' OIH 2½ H. additional	
3100' Oil total fillup	
lime	3411
Total Depth.	

Top Arbuckle 3396