

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.


Plotted
13-11-18 W
986

DARBY PETROLEUM CORP.
Poavoy "A" No. 8

SEC. 13 T. 11 R. 18W.
CWL SW SW

Total Depth. 3427
Comm. 6-17-41 Comp. 7-8-41
Shot or Treated. 500 gal acid.
Contractor
Issued. 8-9-41

County Ellis



CASING.
15" 124'
10" 1188'
7" 3420 CTD.

Elevation.

Production. Pot. 3000 B.
Maximum.

Figures Indicate Bottom of Formations.

shale and shells	260
shale and sand	595
iron	610 ✓
sand shale and shells	850
shale red bed and shells	1183
anhydrite	1217
red bed and shale	1410
shale and shells	1590
salt	1680
shale	1810
shale and lime	2185
lime	2235
shale and lime	2425
shale and shells	2535
shale and broken lime	2600
shale and shells	2700
shale	2875
lime and shale	2955
lime	3419
dolomite	3424
lime	3427
Total Depth.	

Top of Simpson 3399
Arbuckle 3419

RUST and drilling cement at 3420
400' OIH 10 Min.
1700' OIH 1½ hours.

Drilling deeper to 3427 TD.
2700' OIH 3½ hours.
2900' Total Fillup.