

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

Plotted,
E.M.


14-11-18W

SHELL OIL CO., INC.
B.A. Deane No. 3.

SEC. 14 T. 11 R. 18W
NE NW NE
330' f NL 1013' f WL NE $\frac{1}{4}$

Total Depth, 3413³ 3411 SL Corr.
Comm. 8-26-41 Comp. 9-22-41
Shot or Treated.
Contractor. Campbell Drlg. Co.
Issued. 10-18-41

County. Ellis



CASING:

13" 84' Cem.
8 5/8" 1152' Cem.
4 1/2" 3410' Cem.

Elevation.

Indicated Capacity
Production. Echo. Drawdown 8381
Figures Indicate Bottom of Formations. BO, no wtr; Allowed Pot.
3000 B.

sand & shale	280
shale	310
sand	385
shale & red bed	430
sand & pyrite	800 ✓
shale	1035
shale & red bed	1146
anhydrite	1185
shale & red bed	1270
shale	1450
shale & lime sholls	1495
salt	1535
salt & shale	1675
shale & limo	2035
limo & shale brkn	2110
shale & limo	2550
limo & shale brks	2645
shale	2710
shale & lime	2815
shale	2834
limo	2892
limo & shale	2962
limo	3251
conglomerate, shale,	
limo, sand strks,	
chert varicolored	3389
dolomite-poor poro.	3396
shale olive to bright	
green w/red strks,	
sand grains	3409
dolomite, very good	
porosity, saturated w/	
oil	3411
3413 equals 3411 SL Corr.	
Total Depth.	

Top Arbuckle dolo. 3409

1580' oil $\frac{1}{2}$ hr
2510' oil $1\frac{1}{2}$ hrs