


*Plotted gear*  
 14-11-18W

CENTRAL PETRO.CO., INC.  
 Lynn No.1.

SEC. 14 T. 11 R. 18W  
 NEc SW

Total Depth. 3474'  
 Comm. 4-3-40 Comp. 4-20-40  
 Shot or Treated. No.  
 Contractor. Okan Drlg .Co., Inc.  
 Issued. 5-4-40

County. Ellis



CASING:  
 12" 155'  
 85/8" 1163'

Elevation.

Production. Dry

Figures Indicate Bottom of Formations.

surface	30		
shale	90	shale & lime	3301
wtr gravel	120	lime	3394
shale brown	140	conglomerate	3463
gravel	155	core	3474
lime brown & shale	250	Total Depth.	
shale & shells	460		
shale red & lime	535		
iron	550		
lime & iron	600		
shale & lime	663		
sand	835		
shale	915		
shale & shells	1045		
shale sticky & lime	1127		
shale	1155		
lime hrd	1160		
sand hrd	1165		
sand	1195		
sand & shale	1210		
shale & lime	1410		
shale, lime shells, sand	1660		
sand & lime	1800		
lime	1840		
shale & lime	1942		
sand	1954		
shale & lime	2050		
lime	2120		
shale gummy & lime	2178		
shale & lime	2200		
sand & lime	2255		
lime sdy	2265		
shale	2288		
shale & lime	2365		
shale & shells	2415		
shale & lime	2800		
lime w/shale brks	2894		
lime brkn	2956		
lime hrd	2992		
lime	3012		
lime brkn	3018		
lime	3030		
lime brkn	3040		
lime	3220		