

15-11-18W

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - H. H. BLAIR
Farm - Opdyke "A"

No. 4


SEC. 15 T. 11
NE SW SE

R. 18W

Total Depth. 3485'
Comm. 7-26-48
Shot or Treated.
Contractor.
Issued. 10-30-48

Comp. 8-10-48

County. Ellis
KANSAS



Elevation. 1923.9

Production. 92 Bbl.

CASING:

8 5/8" 123' cem w/85 sx.
5 1/2" 3485'

Figures Indicate Bottom of Formations.

shale and shells	485
sand	610
iron pyrite	620
sand and iron pyrite	640
shale and sand	690
sand	875
redbed, sdy & shale	980
redbed and sand	1020
sand	1206
anhydrite	1234
shale and lime	1475
shale and shells	1575
salt, shale and shells	1670
shale and shells	1913
shale & lime shells	2020
shale	2130
lime and shale	2365
shale, lime and shells	2515
shale	2550
shale and shells	2619
shale	2788
shale & lime shells	2890
shale and lime	2930
lime	2992
shale and lime	3046
lime	3063
lime and iron pyrite	3080
lime	3224
lime cherty	3260
lime	3362
lime cherty	3382
lime	3428
lime cherty	3443
lime and shale	3469
shale	3485
total depth	