

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock,

Wichita, Kansas


16-11-18W

Company- SHADE & BERRY
Farm- Wasinger No. 1

SEC. 16 T. 11 R. 18W
SE NE NW

Total Depth. 3533' PB 3281'
Comm. 11-8-57 Comp. 5-13-58
Shot or Treated.
Contractor. Transit Corp.
Issued. 6-28-58

County Ellis
KANSAS



Elevation. 1897' DF

CASING:
13 3/8" 155' cem w/200 sx.
5 1/2" 3531' cem w/250 sx.

Production. 10 BOPD & 16 BWPD
from Kansas City

Figures Indicate Bottom of Formations.

sand 15
clay & gravel 95
sand 130
shale 155
shale & clay 420
shale & shells 493
sand 545
shale & clay 665
shale & clay 700
sand 880
shale & red bed 997
red bed 1196
anhydrite 1235
shale 1260
shale 1450
shale & shells 1758
lime & shale 1853
lime w/shale streaks 1963
lime & shale 2065
shale & lime strks 2165
shale w/lime strks 2241
shale & lime strks 2316
shale w/lime strks 2441
shale 2688
shale & lime strks 2705
shale & lime 2762
shale 2881
lime (Topeka) 2920
lime & shale 2954
lime & shale 3003
lime 3038
shale & lime 3145
lime (Lansing) & shale 3175
lime 3192
lime 3196
lime & shale 3231
lime 3312
lime & shale 3402
conglomerate 3458
Simpson 3484
Arbuckle 3533

TOPS:
Anhydrite 1196
Topeka 2881
Heebner 3104
Toronto 3122
Lansing 3145
Conglomerate 3402
Simpson 3458
Arbuckle 3484

Total Depth
Plugged back to 3281'