

18-11-18W

CONTINENTAL OIL CO.  
John Hancock L.I.Co. No. 2.

SEC.18 T.11 R.18 W  
NEc SE  
330'S 330'W E $\frac{1}{2}$  Cor.

Total Depth. 3498'  
Comm. 10-31-42 Comp. 11-25-42  
Shot or Treated.  
Contractor.  
Issued. 4-10-43

County. Ellis



CASING:  
85/8" 92' Cem.

Elevation.

Production. Dry

Figures Indicate Bottom of Formations.

soil-sand	0-24	shale	2569	lime & shale	3201
gravel	25	shale & lime	2594	brkn lime & shale	3220
shale	66	lime brkn	2600	shale & lime	3223
shale sdy	78	shale & lime	2625	lime	3225
lime	88	lime	2644	shale & lime	3254
shale, lime buttons	96	shale & lime	2667	lime	3286
shale blue&lime shells	157	shale, few lime buttons	2684	shale	3292
shale & chert	249	shale	2710	lime	3302
shale	310	shale & lime	2785	lime & shale	3304
shale & shells	474	lime-shale brks	2829	lime	3306
sand	494	shale	2836	sft lime & chert	3310
ss & shale	555	lime	2850	lime & shale	3320
shale, ss, butts	702	lime & shale	2858	lime hd	3321
sandstone	861	shale	2866	lime	3374
ss & sand	891	shale, hole almost		lgt oil stain 3331-34	
shale	996	blind	2868	oil stain 3374-77	
shale & ss buttons	921	shale	2876	lime brkn	3381
shale & few buttons	1012	lime & shale	2894	lime	3392
shale & buttons	1043	lime brkn	2896	lime very hd	3395
shale & ss	1104	lime & shale	2906	lime & chert buttons	3397
shale & buttons	1194	shale, lime, chert	2908	lime sft	3401
shale few buttons	1215	lime & shale	2920	oil stain 3398-3400	
gyp	1252	lime, chert, shale	2922	lime	3432
shale	1255	lime & shale	2962	lime&shale, hd buttons	3450
shale & sand	1260	lime	2983	lime & shale	3456
shale & gyp	1295	shale & lime	2984	lime, shale, chert	3458
shale & gyp buttons	1342	sand hd & chert	2992	lime & shale	3463
ss rough	1347	lime	2996	lime, shale, chert	
shale - gyp buttons	1377	lime sft	3008	buttons	3464
shale & ss	1408	lime	3010	lime, shale, brkn	3465
shale, few buttons	1438	lime hd	3018	lime, shale, chert	3466
shale	1463	lime & shale	3022	lime & shale	3472
shale & butts	1583	lime	3030	lime, shale, chert	3477
ss & shale	1615	lime & shale	3034	lime & chert	3478
shale & butts	1682	lime & chert buttons	3038	lime, chert, very rough	3480
sdv shale	1741	lime	3070	lime & chert	3481
shale-gyp buttons	1784	lime, last 1' brkn	3072	lime	3482
brkn gyp	1793	lime	3080	lime hd & rough	3483
gyp	1796	brkn lime, shale sft	3086	lime	3486
gyp & shale	1802	lime, chert buttons	3090	lime, first 4" brkn	3487
gyp & shale brks	1894	lime	3094	lime, rough chert &	
shale, gyp, chert buttons	1925	lime hd	3100	shale	3488
shale, gyp, chert	1975	lime, shale	3101	lime	3489
lime hd	1986	lime, shale, chert		lime & shale	3490
shale lime buttons	1990	buttons	3103	lime & chert buttons	3491
lime & shale	2019	lime hd	3105	lime & shale	3492
firm shale & lime	2079	lime & shale (chert)	3106	lime & chert	3493
lime hd	2106	lime & shale	3108	lime	3498
lime & shale	2108	lime&shale (chert-rough)	3109	Total Dept h.	
brkn lime & shale	2110	lime hd & chert	3110	sh dead oil 3483-98	
lime & shale	2150	lime	3112		
shale & lime butts	2195	lime & chert (hd)	3113		
lime	2200	chert very rough	3114		
shale	2206	lime	3121		
shale & few buttons	2231	lime chert buttons	3131		
shale buttons	2255	chert very rough	3132		
shale & lime	2261	first 4" chert-8" lime	3133		
shale & lime bands	2291	lime	3142		
shale & lime	2529	shale & lime	3153		
lime & chert very rough	2530	shale & lime buttons	3159		
lime & chert buttons	2552	lime & shale brks	3181		
shale & lime brkn	2564				