

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock,

Wichita, Kansas

20-11-18W


Company- PHILLIPS PETROLEUM CO.
Farm- Hand No. 3

SEC. 20 T. 11 R. 18W
NW SE SW

Total Depth. 3676
Comm. 12-10-54 Comp. 1-7-55
Shot or Treated.
Contractor.
Issued. 2-12-55

County Ellis

KANSAS



CASING:

9 5/8" 191' cem w/425 sx
7" 3637' cem w/150 sx

Elevation. 2073 DF

Production. Dry

Figures indicate Bottom of Formations.

sand, shale	294
shale	752
shale, shells, anhyd.	1169
shale, anhydrite	1192
redbed, shale, anhyd.	1391
shale, anhyd.	1520
shale, shells	1704
salt, shale, shells	1990
lime, shale	2367
shale	2555
lime, shale	3078
lime	3490
lime, chert	3523
lime	3566
lime, chert	3633
lime	3676
Total Depth	

GW

P.B. 3535
Perf. 7" 3500-09 w/36 shots
Acid w/500. Bailed 22 GW &
scum of oil Plug 3405
Perf. 3382-84 w/8 §
Acid w/500 gals. Bailed
5 BW & 5 1/2 GO in 5 1/2 hrs.
P.B. 3357. Perf. 20 §
3330-35: Acid 500 gal &
1500 gals: bailed 1 GO &
30 BW PH. D & A

Tops:	
Topeka	3061
Heebner	3283
Toronto	3302
Lansing-K. C.	3326
Base K.C.	3558
Congl.	3572
Simpson	3602
Arbuckle	3636

RTD 3638
CTD 3676

RTD 3638
Drlg 3648, Acid 500 gal.
Test 4 1/2 GO + 9 1/2 GW
Drlg 3676 Test 12 GO +
17 GW 4 hrs.
Plug 3622
Perf. 20 § 3596-3601
Perf. 40 § 3582-3592
Acid 3596-3601 & 3582-92
Bailed 33 GW Last hr, 7