

KANSAS DRILLERS LOG

State Geological Survey
WICHITA, BRANCH

S. 20 T. 11 R. 18 ^E/_W
Loc. 1150' FSL & 1020' FWL SE

API No. 15 — 051 — 21,218
County Number

County Ellis

Operator
Vincent Oil Corp.

Address
901 Union Center Bldg., Wichita, Kansas 67202


Well No. #3 Lease Name Wasinger

Footage Location
feet from (N) (S) line feet from (E) (W) line

Principal Contractor Woodman-Iannitti Drlg. Co. Geologist Charles Spradlin

Spud Date 9-10-76 Total Depth 3581' P.B.T.D.

Date Completed 9-21-76 Oil Purchaser Koch Oil Co.



Elev.: Gr. 2028'

DF _____ KB 2032'

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8-5/8"	28#	239'	bulk	150	
Production		5-1/2"	15.5#	3574'		100	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at
2-7/8"	3574'	

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production <u>10-24-76</u>		Producing method (flowing, pumping, gas lift, etc.) <u>pumping</u>			
RATE OF PRODUCTION PER 24 HOURS	Oil <u>165</u> bbls.	Gas MCF	Water <u>None</u> bbls.	Gas-oil ratio	CFPB
Disposition of gas (vented, used on lease or sold)			Producing interval (s)		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator VINCENT OIL CORPORATION DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: OIL WELL

Well No. #3 Lease Name WASINGER

S20 T11 R18 F W

WELL LOG
 Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries. SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Post Rock		40	ELECTRIG LOG TOPS	
Clay, Shale & Sand Streak		140		
Sand		170	Anhydrite	1336
Shale		240	Bs. Anhydrite	1266 1344
Shale		270	Topeka	3010
Sand		380	Heebner	3236
Shale		560	Toronto	3254
Red Bed & Shale		675	Lansing	3276
Shale & Sand Streaks		800	Bs. Kansas City	3504
Sand		1005	Conglomerate	3524
Red Bed		1290	Simpson	3548
Red Bed		1425	Dolomite	3555
Anhydrite		?	Arbuckle	3572
Shale		1500	Total Depth	3581
Shale & Lime		1980		
Lime & Shale		2340		
Lime		3581		
DST #1 - 3031-3055'. 30-45-45-60 min. Weak blow on 1st opening. Died on 2nd opening. Flushed tool, weak blow for 30 min. and died. Recovered 30 ft. mud, no show. IFP 43-43#, FFP 43-43#, ISIP 1205#, FSIP 1056#.				
DST #2 - 3172-3210'. 30-45-45-60 min. Strong blow throughout. Recovered 20 ft. oil cut muddy water, 125 ft. slightly oil cut muddy water, 185 ft. muddy water. IFP 65-119#, FFP 130-184#, ISIP 368#, FSIP 368#.				
DST #3 - 3324-3364'. 30-45-45-60 min. Fair blow throughout. Recovered 30 ft. gas in pipe, 30 ft. gassy muddy oil, 10 ft. gassy oil cut muddy water, 110 ft. slightly oil cut muddy water. IFP 43-54#, ISIP 701#, FFP 65-97, FSIP 680#.				
DST #4 - 3426-3510'. 30-30-30-30 min. Weak blow 1st opening, died 23 min. in 2nd opening. Flushed tool with weak blow. Recovered 50 ft. mud, no show of oil. IFP 54-54#, ISIP 895#, FFP 54-54#, FSIP 895#.				
DST #5 - 3558-3574'. 30-45-45-60 min. Strong blow throughout. Recovered 120 ft. gas in pipe, 1160 ft. clean gassy oil. IFP 43-238#, ISIP 1109#, FFP 259-444#, FSIP 1095#.				
DST #6 - 3574-3581'. 30-45-45-60 min. Strong blow throughout. Recovered 120 ft. gas in pipe, 2350 ft. clean gassy oil, 40 ft. gassy muddy oil. IFP 65-605#, ISIP 1024#, FFP 665-884#, FSIP 1024.				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received _____
 Signature Vincent F. Heebush
 President
 Title
 December 7, 1976
 Date

2L6H8

K. T. WOODMAN
RES. PHONE 733-0418
OFF. PHONE 265-7650
WICHITA, KANSAS

15-051-21218

D. J. IANNITTI
PHONE 792-2921
GREAT BEND, KANSAS

20-11-18W

WOODMAN & IANNITTI DRILLING COMPANY
Rotary Drilling Contractors

1008 UNION NATIONAL BUILDING
WICHITA, KANSAS 67202

September 22, 1976

State Geological Survey
WICHITA, BRANCH

Company;	Vincent Oil Corporation
Farm;	#3 Wasinger
Location;	NE SW SE
Section;	20-11-18W
County;	Ellis
Contractor;	Woodman & Iannitti Drilling Co.
Comm;	Sept. 10, 1976
Compl;	Sept. 21, 1976
Total Depth;	3581'
Casing;	8 5/8 @ 239 w/150 sx. 5 1/2 @ 3574 w/100 sx.

Figures Indicate Bottom Of Formations:

40	Post Rock
140	Clay & Shale & Sand Streak
170	Sand
240	Shale
270	Shale
380	Sand
560	Shale
675	Red Bed & Shale
800	Shale & Sand Streaks
1005	Sand
1290	Red Bed
1425	Red Bed
?	Anhy
1500	Shale
1980	Shale & Lime
2340	Lime & Shale
2790	Lime
3055	Lime
3180	Lime
3300	Lime
3430	Lime
3570	Lime
3581	Lime

I certify the above to be a true and correct copy of the driller's log to the best of my knowledge and belief.

Woodman & Iannitti Drilling Co.

K. T. Woodman
K. T. Woodman