

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bldg. Wichita, Kansas


Company - MID-STATES OIL COMPANY
Farm Wasinger 'A' No. 1

SEC. 21 T. 11 R. 18W
SE NE SE

Total Depth. 3594'
Comm. 1-17-48 Comp. 2-9-48
Shot or Treated.
Contractor
Issued 3-20-48

County. Ellis

KANSAS



Elevation. 2075 *ft*

Production. Pot. 3000 Bbls.

CASING:

10-3/4" 1345' Com. W/600 Sx.
7" OD 3592' Com. W/300 Sx.

Figures indicate Bottom of Formations.

surface rock	75
shale	175
sand & shale	215
shale	245
shale & iron	345
shale	470
sand & shale	580
sand	775
shale & shells	1340
anhydrite	1385
shale	1410
shale & shells	1975
shale & lime	2345
lime	2901
shale	2925
shale & some lime	3000
lime & shale	3065
lime	3095
lime & shale	3130
lime	3205
lime & shale	3290
lime	3361
lime & oil	3387
lime	3445
lime brkn & shale	3465
lime	3496
lime & shale	3530
lime	3537
conglomerate	3570
lime & shale	3585
shale	3592
dolomite	3594
Total Depth	

SAMPLE TOPS:

Anhydrite	1342
Topoka	3016
Hochner	3241
Lansing	3283
Conglomerate	3536
Simpson	3569
Arbuckle	3589